#REF! **#REF!**

FOUNDATIONS AND SUBSTRUCTURE

item	description	quantity	unit		rate		total
	reduce dig	102	m3	£	17.25	£	1,759.50
	excavate foundation trench	71	m3	£	20.70	£	1,469.70
	disposal by tipper lorry	173	m3	£	23.00	£	3,979.00
	compact bottoms of excavations	1	Item	£	230.00	£	230.00
	allow to keep excavations free from water	1	item	£	230.00	£	230.00
	Gen 3 concrete to strip foundations	32	m3	£	120.75	£	3,864.00
	100mm thick concrete blockwork	57	m2	£	37.95	£	2,163.15
	wall ties	1	Item	£	51.75	£	51.75
	concrete cavity fill	1	Item	£	345.00	£	345.00
	100mm wide dpc	71	m	£	4.60	£	326.60
	cavity tray - **Rate Only**	0	m	£	14.95	£	-
	New floor						
	Beam and Block floor	146	m2	£	43.13	£	6,296.25
	1200 guage polythene dpm including laps on 50mm sand blinding	146	m2	£	4.60	£	671.60
	500 gauge isolating membrane	146	m2	£	3.45	£	503.70
	100mm kingspan floor insulation	146	m2	£	17.25	£	2,518.50
	65mm floor screed	146	m2	£	28.18	£	4,113.55
					To summary	**£**	**28,522.30**